



कार्यालय: राँची नगर निगम, राँची।

(जलापूर्ति शाखा)

कचहरी रोड, राँची, पिन - 834001

e-mail :- support@ranchimunicipal.com

पत्रांक : 116/WSS

दिनांक : 5/03/2018

अतिअल्पकालीन निविदा आमंत्रण सूचना

1. विज्ञापनदाता का पदनाम :- कार्यपालक अभियंता, राँची नगर निगम, राँची।
2. निविदा प्राप्त करने की तिथि एवं समय :- 22/03/2018 को 02:00 बजे अपराह्न तक।
3. निविदा खोलने की तिथि एवं समय :- 23/03/2018 को 02:30 बजे अपराह्न के बाद।
4. परिमाण विपत्र Download की तिथि :- 12/03/2018 से 19/03/2018 तक।
5. निविदा प्राप्ति का स्थान :- जलापूर्ति शाखा, राँची नगर निगम, राँची


| क्र० | वार्ड नं० | योजना का नाम | प्राक्कलित राशि | परिमाण विपत्र का मूल्य (लौटाने योग्य नहीं) | अग्रधन की राशि | कार्य समाप्ति की अवधि (कार्यादश की तिथि) |
|------|-----------|---|-----------------|--|----------------|--|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | 22 | जलापूर्ति शाखा, राँची नगर निगम अन्तर्गत वार्ड नं० 22 में पुराने गोदाम के बगल में दो कमरों का भण्डार-गृह निर्माण कार्य। | 545930.00 | 5000/- | 11000/- | 120 दिन |
| 2 | 46 | जलापूर्ति शाखा, राँची नगर निगम अन्तर्गत डोरण्डा अंचल अन्तर्गत वार्ड नं० 46 में गोदाम के बगल डोमटोली में दो कमरों का भण्डार-गृह निर्माण कार्य। | 545930.00 | 5000/- | 11000/- | 120 दिन |

1. निविदा के साथ निम्नलिखित कागजात निम्न क्रम में संलग्न करना अनिवार्य होगा।

- (क) a- परिमाण विपत्र का मूल्य (डिमाण्ड ड्राफ्ट मूल रूप में)
- b- अग्रधन की राशि (मूल रूप में)
- c- राँची नगर निगम/नगर विकास एवं आवास विभाग में निबंधन की प्रति।
- d- वैध चरित्र प्रमाण पत्र (छायाप्रति)
- e- G.S.T निबंधन से संबंधित प्रमाण पत्र
- f- पैन (छाया प्रति)
- g- Download किया गया एन0 आई0 टी0 के साथ परिमाण विपत्र।

(ख) उपरोक्त क्रम में संबंधित दस्तावेज संलग्न करने के उपरान्त प्रत्येक पृष्ठ में (अग्रधन की राशि एवं डिमाण्ड ड्राफ्ट को छोड़कर) पृष्ठ संख्या अंकित कर स्वप्रमाणित (हस्ताक्षर) किया जाना आवश्यक है।

2. बिना कारण बताये निविदा या किसी विशेष कार्य को रद्द करने अधिकार अधोहस्ताक्षरी को सुरक्षित होगा।
3. निविदा के साथ अग्रधन की राशि राष्ट्रीय बचत प्रमाण पत्र (8वें निर्गम) तीन या पाँच वर्षीय सावधि पासबुक (पोस्ट ऑफिस का) जो नगर आयुक्त, राँची नगर निगम, राँची के पदनाम से प्रतिज्ञित (प्लेज) हो, देय होगा।





4. परिमाण विपत्र का मूल्य (जो किसी भी परिस्थिति में वापस नहीं होगा), रांची नगर निगम में डिमांड ड्राफ्ट (प्रत्येक ग्रुप के लिये अलग से) नगर आयुक्त, रांची नगर निगम, रांची के नाम से जमा करना होगा एवं परिमाण विपत्र रांची नगर निगम के वेबसाइट www.ranchimunicipal.com से उपरोक्त निर्धारित तिथि के अन्दर Download किया जाना है तथा डिमांड ड्राफ्ट (प्रत्येक ग्रुप के लिये अलग से) संख्या उसमें अंकित करते हुये निविदा के साथ अलग Cover में निर्धारित तिथि को निगम में जमा करेंगे।
 5. इस निविदा के संबंध में विस्तृत जानकारी निविदा प्रकाशन के उपरांत किसी कार्य दिवस में नगर निगम के जलापूर्ति शाखा से प्राप्त किया जा सकता है।
 6. कार्य की प्राक्कलित राशि घट या बढ़ सकती है। तदनुसार अग्रधन की राशि एवं परिमाण विपत्र के मूल्य में परिवर्तन हो सकता है। अनुमोदित परिमाण विपत्र के अनुसार ही उक्त राशि देय होगी।
 7. सशर्त निविदा मान्य नहीं होगा।
 8. अनुसूचित दर से 10 प्रतिशत से कम दर मान्य नहीं होगा।
 9. निविदा के पूर्व स्थल का निरीक्षण संवेदक कर लें तथा स्थिति से संतुष्ट होकर ही निविदा दे। इस संबंध में किसी भी प्रकार का दावा मान्य नहीं होगा। संवेदक को किसी प्रकार का यंत्र-सयंत्र एवं सामग्री निगम द्वारा उपलब्ध नहीं कराया जायेगा।
 10. जिन संवेदको द्वारा ससमय कार्य पूर्ण नहीं किया गया है तथा अभी भी कार्य लंबित है, उन संवेदको को कार्य आवंटित नहीं किया जायेगा।
 11. आवंटित कार्य का किसी भी परिस्थिति में Sub-letting मान्य नहीं होगा।
 12. किये गये कार्य का रख-रखाव 3 वर्षों तक संवेदक के द्वारा किया जायेगा। इसके लिए सुरक्षित राशि 3 वर्षों की अवधि पूरा होने के पश्चात् ही कार्य संतोषप्रद पाये जाने पर विमुक्त की जायेगी तथा EMD की राशि कार्य पूर्ण होने के उपरान्त 06 माह में विमुक्त की जायेगी।
 13. कार्य स्थल पर कार्य की विवरणी का सूचना पट्ट संबंधित सहायक अभियंता से प्रारूप अनुमोदित कराकर लगाना अनिवार्य होगा।
 14. कार्य आवंटित किये जानें के पश्चात् संवेदक जलापूर्ति शाखा में शेष अग्रधन की राशि राष्ट्रीय बचत प्रमाण पत्र (8वें निर्गम) तीन या पाँच वर्षीय सावधि पासबुक जो नगर आयुक्त, रांची नगर निगम, रांची के पदनाम से प्रतिज्ञित (प्लेज) हो, एक सप्ताह के अन्दर जमा कर एकरारनामा करना सुनिश्चित करेंगे। एकरारनामा ससमय नहीं किये जाने पर आवंटित कार्य रद्द कर दिया जायेगा तथा भविष्य में कोई भी कार्य आवंटित नहीं किया जायेगा न ही कार्य आवंटन के संबंध में कोई दावा मान्य होगा।
 15. संवेदक कार्य समाप्ति के पश्चात् कार्यालय को सूचित करेंगे। सूचना नहीं प्राप्त होने पर ऐसा समझा जायेगा की संवेदक द्वारा निर्धारित अवधि में कार्य पूर्ण नहीं कराया गया है एवं समय वृद्धि किसी भी परिस्थिति में नहीं दी जायेगी।
- उपरोक्त निर्देशों का अनुपालन नहीं किये जाने पर संबंधित निविदायें अमान्य कर दी जायेगी।

02/03/18
कार्यपालक अभियंता
रांची नगर निगम, रांची।
03/3/18

RANCHI MUNICIPAL CORPORATION, RANCHI

BOQ for construction of Two Rooms Store of size (14'5x13'0") under Ranchi Municipal Corporation (Water Supply Section) in Ward No. 46 Near Old Store Room of Doranda Circle, Domtoli.

| Sl. No. | Items of work | Qty. | Unit | Rate | Amount |
|---------------|---|-------|------|---------|----------|
| 1. 5.1.1 | Earth work in excavation in foundation trenches in ordinary soil (vide classification of soil item-A) and disposal of excavated earth as obtained to a distance up to 50 M. including all lifts, levelling, ramming the foundation trenches removing roots of trees, shrubs all complete as per approved design, building specification and direction of E/I. | 10.76 | m3 | 102.1 | 1098.60 |
| 2. 5.1.7 | filling in foundation trenches and plinth in layer not exceeding 150mm thick well water rammed, fully compacted and fine dressed with earth obtained from excavation of foundation trenches with in lead of 50m and lift of 1.5m all complete as per building as per specification & direction of E/I | 11.50 | m3 | 37.17 | 427.46 |
| 3. 5.1.10 | Providing coarse clean sand in filling in foundation trenches or in plinth including ramming and watering in layers not exceeding 150 mm thick with all leads and lifts including cost of all materials, labour, royalty and taxes all complete as per building specification & direction of E/I. | 3.48 | m3 | 228.47 | 795.08 |
| 4. 5.6.1 | Providing designation 75A one brick flat soling joints filled with local sand including cost of watering taxes royalty all complete as per building specification and direction of E/I. | 45.06 | m2 | 233.78 | 10534.13 |
| 5. 5.3.2 | Providing P.C.C M 150 in nominal mix (1:2:4) in foundation with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position, vibrating, skirting, curring, taxes and royalty complete as per building specification and direction of E/I | 0.85 | m3 | 5913.66 | 5026.61 |
| 6. 5.3.5.1 | Providing R.C.C M 200 in nominal mix of (1:1.5:3) in footing & plinth with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position, vibrating striking, curing (but excluding the cost of reinforcement, taxes and royalty all complete, as per specification and direction of E/I. | 3.47 | m3 | 6543.32 | 22705.32 |
| 7. 5.3.11 | Providing R.C.C M 200 in nominal mix of (1:1.5:3) in Tie beam of all types with approved quality of stone chips 20 mm to 6mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, centering shuttering, mixing cement concrete in mixer and placing in position, vibrating striking, curing (but excluding the cost of reinforcement, taxes and royalty all complete, as per specification and direction of E/I. | 1.87 | m3 | 8928.5 | 16696.30 |
| 8. 5.3.14 | Providing R.C.C M 200 in nominal mix of (1:1.5:3) in columns with approved quality of stone chips 20 mm to 6mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, centering shuttering, mixing cement concrete in mixer and placing in position, vibrating striking, curing (but excluding the cost of reinforcement, taxes and royalty all complete, as per specification and direction of E/I. | 2.95 | m3 | 7647.84 | 22561.13 |





| | | | | | |
|---------------------|---|-------|------|---------|-----------|
| 9. 5.2.11 | Providing designation 75A brick work in C.M.(1:6) in superstructure with approved quality of clean coarse sand of F.M. 2 to 2.5 including providing 10 mm thick mortar joints, cost of screening materials, raking out joints to 15 mm depth, curing, taxes and royalty all complete as per building specification and direction of E/I. | 26.67 | m3 | 4011.07 | 106975.24 |
| 10. 5.3.16. 1 | Providing 25 mm thick damp proof course with cement concrete M-200 with nominal mix of (1:1.5:3) with quality of stone chips of 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, and mixing cement concrete in mixer with 5% cico or any other approved water proffing compound and placing in position, striking, curing, taxes and royalty all complete, as per building specificaiton and direction of E/I. | 7.36 | m2 | 189.92 | 1397.81 |
| 11. 5.3.8.1 | Providing R.C.C M 200 in nominal mix of (1:1.5:3) in lintel with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, centering shuttering, mixing do all complete as per specification and direction of E/I. | 2.25 | m3 | 7117.44 | 16014.24 |
| 12. 5.3.11 | Providing R.C.C M 200 in nominal mix of (1:1.5:3) in beam of all types with approved quality of stone chips 20 mm to 6mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, centering shuttering, mixing cement concrete in mixer and placing in position, vibrating striking, curing (but excluding the cost of reinforcement, taxes and royalty all complete, as per secification and direction of E/I. | 1.12 | m3 | 8928.5 | 9999.92 |
| 13. 5.3.9.1 | Providing R.C.C M 200 in nominal mix of (1:1.5:3) in roof slab with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, centering shuttering, mixing do all complete as per specification and direction of E/I. | 6.95 | m3 | 8235.61 | 57237.49 |
| 14. 5.3.3 | Providing P.C.C M 100 in nominal mix (1:2:4) in foundation with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position, vibrating, skirting, curring, taxes and royalty complete as per building specification and direction of E/I. | 3.51 | m3 | 5913.66 | 20756.95 |
| 15. 5.6.7 | Providing 25 mm thick first class patent stone flooring (1:2:4) with stone chips in two layers, bottom layer 19mm. Thick (1:2:4) with 12 mm to 6 mm size graded stone chips and top layer 6mm, thich (1:2) with 6 mm down stone chips, in panels including cost of curing, finishing the surface smooth by rubbing with carborandum stone, taxes and royalty with all complete as per building specification and direction of E/I. | 1.86 | m2 | 271.41 | 504.82 |
| 16. 5.7.11 | Providing 1.5 mm cement punnig including curing, carriage of water with all leads and lifts as per building specificaiton and direction of E/I. | 34.84 | m2 | 45.17 | 1573.72 |
| 17. 5.5.13 | Providing and fixing fan hook of 16 mm dia. M.S. bar 1 metre long bent to required size and shape, placed in position and fixed in R.C.C. slab/beam at the time of casting all complete as per building specification and direction of E/I. (where material in not supplied by deppt.) | 2.00 | Nos. | 97.03 | 194.06 |
| 18. 5.5.29 | Supplying, fitting and fixing 20 guage G.C.I sheet gate fitted on M.S Angle frame of size 60X60X60mm including cost of fabrication, providing necessary locking arrangement with haskal and domny duly fixed in PCC (1:2:4) blocks of required size, applying a priming red lead paint over steel work, taxes all complete as per drawing specification and direction of E/I. | 5.20 | m2 | 2907.19 | 15117.39 |

Mm

OK

| | | | | | |
|-----------------------------------|--|----------|------|----------|------------------|
| 19. 5.8.41 + 5.8.45 | Providing primer two coats of synthetic enamel paint of approved shade with primer one coat of red lead paint of approved make over new steel surface including preparing the surface after cleaning, removing dust, dirt, scales smokes and grease and cleaning the surface thoroughly including cost of scaffolding and taxes all complete as per building specification and direction of E/I. | 11.71 | m2 | 95.11 | 1113.74 |
| 20. 5.7.14 | Providing 12 mm thick water proof cement plaster (1:3) with clean coarse sand of F.M 1.5 with 5% cico or any other approved water proofing compound including screening, curing with all leads and lifts of water, scaffolding taxes and royalty all complete as per building specification and direction of E/I. | 46.95 | m2 | 154.79 | 7267.39 |
| 21. 5.7.3 | Providing 12 mm thick C.P.(1:6) with clean coarse sand of F.M. 1.5 including screening, curing with all leads and lifts of water scaffolding taxes and royalty all complete as per building specification and direction of E/I. | 274.10 | m2 | 125.34 | 34355.69 |
| 22. 5.7.6 | Providing 6 mm thick C.P.(1:4) in ceiling with clean coarse sand fo F.M. 1.5 including screening, curing with all leads and lifts of water scaffolding taxes and royalty all complete as per building specification and direction of E/I. | 40.07 | m2 | 133.78 | 5360.56 |
| 23. 5.8.24 | Providing two coats of snowcem of approved shade and make over a coat of cement primer on new surface including preparing the plastered surface smooth with sand paper, scaffolding, curing and taxes all complete as per building specification and direction of E/I. | 303.37 | m2 | 81.14 | 24615.44 |
| 24. 5.5.4. 5.5.5 (a+b+c) | Providing Tor steel reinforcement of 10 mm, 12 mm & 16 mm dia bars as per approved design and drawing excluding carriage of Rods (straight or in coils) to work site, cutting, bending and binding with annealed wire with cost of wire, removal of rust, placing the rods in position all complete as per building specification and direction of E/I. | 2.08 | M.T. | 53433.91 | 111142.53 |
| 25 | Carriage of Materials | | | | |
| (i) | Sand (Lead 14 KM) | 45.09 | m3 | 360.06 | 16235.00 |
| (ii) | Stone Chips (Lead 22 KM) | 55.38 | m3 | 462.56 | 25617.00 |
| (iii) | Bricks (Lead 08 KM) (Rate for One Thousand) | 12291.00 | Nos. | 688.68 | 8465.00 |
| TOTAL:- | | | | | 543788.61 |
| Say Rs. | | | | | 543789.00 |

Junior Engineer
WSS, RMC, Ranchi.

Assistant Engineer
WSS, RMC, Ranchi.

B.O.R. approved from Sl. No- 01. to 25 amounting
Rs. 5,43,789.00 (Five lakh forty three thousand seven
hundred eighty nine) only.

Executive Engineer
WSS, RMC, Ranchi.

Request for Proposal (R.F.P)

TO BE FILLED BY THE TENDERER

TENDERERS MUST QUOTE THEIR RATE AS PER DIRECTION GIVEN BELOW.

**Construction of Two Rooms Store of size (14'5x13'0") under Ranchi Municipal Corporation
(Water Supply Section) in Ward No. 46 Near Old Store Room of Doranda Circle, Dومتولي.**

1. I/We am/are ready to execute the work on (in figure)% (in words)
..... **Percent below** in the
Department Rates for each item of work as furnished by the Department in this tender documents.

2. I/We am/are ready to execute the work on **Departmental rates** for each item of work as
furnished by the department in this Tender document.

3. I/We am/are ready to execute the work on (in figure)% (in words)
..... **Percent above** in the
Department Rates for each item of work as furnished by the Department in this tender documents.

NOTE:

Strike out which are not applicable.

Rates quoted on percent basis "above" or "below" must be written in figures and words both where the space is provided, failing which the tender may be rejected.

FULL NAME OF THE TENDERER

(IN BLOCK LETTER):

.....

FULL PERMANENT ADDRESS:

.....

.....

.....

FULL LOCAL ADDRESS:

.....

.....

.....

NAME & SIGN. OF THE CONTRACTOR.



